

**MODEL 6200 - DRY
DUAL PLACEMENT TOOLBAR SPECIFICATIONS**

**Available Sizes (working widths)
20' (8 row) & 30' (12 row) 40' (16 row)**

Mainframe & Wing Tubing	7" x 7" x 3/8" wall square tubing	7" x 7" x 3/8" wall square tubing
Front Hitch	Rigid - 7" x 7" x 1/2" wall square tube (rigid)	Extendable - 8" x 8" x 3/8" over 7" x 7" x 1/2" sq. tube
Transport Width	14' 6"	14' 6"
Transport Height	9'	9'
Mainframe Wheels	18.4 x 26 - 10 ply	18.4 x 26 - 10 ply
Wing Wheels - swivel caster	12.5L x 15 - 8 ply	12.5L x 15 - 8 ply
Front Folding Design	Standard Equipment (Note: 20' does not fold)	Standard Equipment - retracting hitch
Hydraulic Transport Hitch	Standard Equipment	Standard Equipment
Rear Hitch Assembly	Rigid with Telescoping Tongue	Rigid with Telescoping Tongue
Rephasing Lift System	Standard Equipment	Standard Equipment
Safety Lighting System	Standard Equipment	Standard Equipment
Combination Hitch Clevis (Single/Double)	Standard Equipment	Standard Equipment
Patented Midmount Design	Standard Equipment	Standard Equipment
6 Ton Stainless Dry Fertilizer Air System (304 Stainless)	Optional	Optional
Rigid Mount Edge-Bent Shank w/20" Spring Loaded Coulter	Optional	Optional
Auto Reset Mount w/20" Spring Loaded Coulter	Optional	Optional
Row Pro 230 (Parallel Linkage Unit)	Optional	Optional
Row Pro 300 - Parallel Linkage/Triple Coulter Combo Row Unit	Optional	Optional
Row Pro 300 - Parallel Linkage Standard Row Unit w/18" Trash Titan Disk Sealer	Optional	Optional
18" Trash Titan Disk Sealer - Notched or Smooth Blades	Optional	Optional
Progressive's Flat Fold Row Markers w/Sequence Valve	Optional	Optional
Monitor Mounting Bracket	Optional	Optional
3-way Electric Control Valve	Optional	Optional
Bin Level & Product Metering Monitor	Optional	Optional
Digistar Drybox Scale	Optional	Optional

Progressive Farm Products, Inc.

19500 N. 1425 East Road

Hudson, IL 61748

(309) 454-1564

Specifications subject to change without notice or obligation.