

**MODEL 6200 - DRY  
DUAL PLACEMENT TOOLBAR SPECIFICATIONS**

**Available Sizes (working widths)  
20' (8 row) & 30' (12 row)                      40' (16 row)**

|  |   |  |
|--|---|--|
| Mainframe & Wing Tubing  | 7" x 7" x 3/8" wall square tubing               | 7" x 7" x 3/8" wall square tubing                        |
| Front Hitch  | Rigid - 7" x 7" x 1/2" wall square tube (rigid) | Extendable - 8" x 8" x 3/8" over 7" x 7" x 1/2" sq. tube |
| Transport Width  | 14' 6"  | 14' 6"   |
| Transport Height   | 9'  | 9'   |
| Mainframe Wheels   | 18.4 x 26 - 10 ply                              | 18.4 x 26 - 10 ply                                       |
| Wing Wheels - swivel caster  | 12.5L x 15 - 8 ply                              | 12.5L x 15 - 8 ply                                       |
| Front Folding Design   | Standard Equipment<br>(Note: 20' does not fold) | Standard Equipment - retracting hitch                    |
| Hydraulic Transport Hitch  | Standard Equipment                              | Standard Equipment                                       |
| Rear Hitch Assembly  | Rigid with Telescoping Drawbar                  | Rigid with Telescoping Drawbar                           |
| Rephasing Lift System  | Standard Equipment                              | Standard Equipment                                       |
| Safety Lighting System   | Standard Equipment                              | Standard Equipment                                       |
| Combination Hitch Clevis (Single/Double)                                       | Standard Equipment                              | Standard Equipment                                       |
| Patented Midmount Design   | Standard Equipment                              | Standard Equipment                                       |
| 6-Ton Poly Tank - Dry Fertilizer Air System with Newmatics Metering System     | Optional  | Optional   |
| Rigid Mount Edge-Bent Shank w/20" Spring Loaded Coulter                        | Optional  | Optional   |
| Auto Reset Mount w/20" Spring Loaded Coulter                                   | Optional  | Optional   |
| Row Pro 300 - Parallel Linkage - Auto-Reset Row Unit                           | Optional  | Optional   |
| Row Pro 300 - Parallel Linkage/Triple Coulter Combo Row Unit                   | Optional  | Optional   |
| Row Pro 300 - Parallel Linkage Standard Row Unit w/18" Trash Titan Disk Sealer | Optional  | Optional   |
| 18" Trash Titan Disk Sealer - Notched or Smooth Blades                         | Optional  | Optional   |
| Progressive's Flat Fold Row Markers w/Sequence Valve                           | Optional  | Optional   |
| Monitor Mounting Bracket   | Optional  | Optional   |
| Bin Level & Product Metering Monitor   | Optional  | Optional   |
| Drybox Scale   | Optional  | Optional   |

**Progressive Farm Products, Inc.**

**19500 N. 1425 East Road**

**Hudson, IL 61748**

**(309) 454-1564**

Specifications subject to change without notice or obligation.