

MODEL 7200 NH3 TOOLBAR SPECIFICATIONS

Available Sizes (working widths)

30' (12 row) & 40' (16 row)

60' (24 row)

	30' (12 row) & 40' (16 row)	60' (24 row)
Mainframe & Wing Tubing	7" x 7" x 3/8" wall square tubing	7" x 7" x 3/8" wall square tubing
Front Hitch - Rigid for 30'	7" x 7" x 1/2" wall sq. tube (rigid)	
Front Hitch - Retracting for 40' & 60'	8" x 8" x 3/8" over 7" x 7" x 1/2" Tube	10" x 10" x 3/8" over 8" x 8" x 3/8" Tube
Transport Width	14' 6"	16'
Transport Height	9' with optional markers	9' with optional markers
Mainframe Wheels	12.5L x 15 - 8 ply	16.5 x 16.1 - 10 ply
Wing Wheels	12.5L x 15 - 8 ply	16.5 x 16.1 - 10 ply
Front Folding Design	Standard Equipment	Standard Equipment
Hydraulic Transport Hitch	Standard Equipment	Standard Equipment
Rear Hitch Assembly	Self-leveling w/Telescoping Tongue	Self-leveling w/Telescoping Tongue
Rephasing Lift System	Standard Equipment	Standard Equipment
Safety Lighting System	Standard Equipment	Standard Equipment
Combination Hitch Clevis (Single/Double)	Standard Equipment	Standard Equipment
Rigid Mount Edge-Bent Shank w/20" Spring Loaded Coulter	Optional	Optional
Auto Reset Mount w/20" Spring Loaded Coulter	Optional	Optional
Row Pro 300 - Parallel Linkage Auto-Reset Row Unit	Optional	Optional
Row Pro 300 - Parallel Linkage/ Triple Coulter Combo Row Unit	Optional	Optional
Row Pro 300 - Parallel linkage Standard Row Unit w/18" Trash Titan Disk Sealer	Optional	Optional
18" Trash Titan Disk Sealer	Optional	Optional
Flat Fold Row Markers	Optional	Optional
Monitor Mounting Bracket	Optional	Optional
3-way Electric Control Valve	Optional	Optional
Water Rinse Tank with Toolbox	Optional	Optional

**Progressive Farm Products, Inc.
19500 N. 1425 East Road
Hudson, IL 61748
(309) 454-1564**

Specifications subject to change without notice or obligation.